



ROWAD
MODERN ENGINEERING

Subcontractor Management Process P-OP-01

Prepared by:

Maha Iskander
Quality Assurance Manager

Mahmoud Mahlab
Operation Manager

Reviewed by:

Mohamed Ragab
COO

Approved by:

Mohamed Mahlab
CEO

Dec 2021

	Subcontractor Management Process		
	Effective Date: Dec, 2021	Rev. No.: 00	Doc. No.: P-OP-01

1. OBJECTIVES

The objective of the subcontractor management process is to ensure that subcontractors establish, document, follow and maintain adequate RME system, and to ensure the proper supervision and flow down of the project requirements to the subcontractors.

2. STAKHOLDER

- Operation dept
- Quality Assurance Department
- Quality Control Department
- Contracts and Claims Department
- PM
- CM
- Safety Officer
- S/C
- TOM

3. LIABLE STAKEHOLDER

- S/C
- Quality Control Department
- Quality Assurance Department
- PM
- CM
- TOM
- Safety Officer

4. TERMS AND DEFINITION

- PM: Project Manager
- CM: Construction Manager
- TOM: Technical Office Manager
- S/C: Subcontractor
- OMM: Operation and Maintenance Manual
- MOM: Minutes of Meetings
- NCR: Non-Conforming Report
- ITP: Inspection and Test Plan

- IR: Inspection Request
- MSDS: Material Safety Data Sheet
- CV: Curriculum Vitae Latin for "course of life"
- TBT: Toolbox Talks
- E1 Log: Drawing's log
- E2 Log: Material submittal log

5. RELATED DOCUMENTED INFORMATION

- Minutes of meeting Form, (F-P-QD-06-02)
- Audit Report Form, (F-P-QD-01-05)
- Site NCR (F-P-QD-02-02)
- Method Statement, (F-P-QD-07-05)
- ITP (F-P-QD-07-06)
- RFI, (F-PQP-01-03)
- RFI log, (F-OP-04-01)
- MIR (F-P-QD-07-01)
- Snag List, F-P-OP-07-05
- OMM, F-P-OP-07-04
- IR, (F-PQP-01-05)

6. PROCESS DETAILS

6.1. PROCESS INPUT

- Subcontract

6.2.PROCESS OPERATION

Sr.	Process Cycle description	Responsibility	Form
1	Subcontractor Types The types of subcontractors in RME are divided as follows: • Type 1: Potential S/C (Pre-bid agreement) • Type 2: Nominated S/C • Type 3: Supply-Apply S/C (Procurement, MEP)		

	Subcontractor Management Process		
	Effective Date: Dec, 2021	Rev. No.: 00	Doc. No.: P-OP-01

Sr.	Process Cycle description	Responsibility	Form
	Type 4: Apply S/C (operation)		
2	Selection and Management of Subcontractors RME PM shall determine which of the work activities of the project to be subcontracted and arrange for Subcontractor selection accordingly. Refer to Project launching process(P-TN-02), Vendor selection and bidding process(P-VMO-01), Subcontractor agreement process (P-CN-01).	RME PM	
3	S/C Shall submit the organization chart including their PM CV for approval for type 1&2&3 as mentioned in step 1.	S/C	
4	RME safety officer shall hold Toolbox Talks (TBT) on weekly basis to the Subcontractors.	safety officer	
5	S/C management system shall be audited by RME QA team, when required.	QA team	Audit Report (F-P-QD-01-05)
6	Kick-off Meeting Kick-off meeting shall be conducted by the PM after the subcontract agreement (maximum of 3 working days) to discuss all the requirements as mentioned in the below points. and the MOM shall be signed by all parties. TOM shall prepare and hand over a project file to be received and signed by S/C, includes but not limited to: Quality plan, safety plan, Drawings, project forms, project specs, etc.	PM	MOM (F-P-QD-06-02)

Subcontractor Management Process

Effective Date: Dec, 2021

Rev. No.: 00

Doc. No.: P-OP-01

[illegible]

Sr.	Process Cycle description	Responsibility	Form
6.6	F. RFI (Refer to process (P-OP-04)) - RFIs raised by RME S/C shall be routed to the client through RME PM and TOM. - A log of RFIs shall be maintained and outstanding RFIs to be brought to PM and TOM attention for proper action.	S/C PM TOM	RFI (F-PQP-01-03) RFI Log (F-OP-04-01)
6.7	G. Material Inspection (Refer to process (P-QD-11)) RME QC Engineer shall inspect the S/C engineering material in factory during fabrication and before packaging (if required), in addition to site inspection and notify the S/C and any concerned party for the status of the inspected material.	RME QC Engineer	MIR (F-P-QD-07-01)
6.8	H. Work Inspection (Refer to process (P-QD-12)) The S/C shall follow the approved Method Statements and ITPs in site execution and inspections, then notify RME CM of any completed work/product ready for inspection through IR and/or MIR.	S/C	Method Statement (F-P-QD-07-05) ITP (F-P-QD-07-06) IR (F-PQP-01-05) MIR (F-P-QD-07-01)
6.9	I. Control of Non-Conforming Products (Refer to process (P-QD-02)) - When a Non-Conformity Report (NCR) is raised on the S/C, corrective action shall be taken within 7 days to eliminate the causes of non-conformity and to avoid recurrence. - NCR closure shall be as per RME/Client requirements, as work must be rectified and offered for inspection again through IR.	S/C	NCR (F-P-QD-02-02) IR (F-PQP-01-05)

Sr.	Process Cycle description	Responsibility	Form
6.10	J. Progress Meetings - Weekly meeting to be conducted by PM/CM with the S/C to follow-up on his progress, issues, NCRs, rejected works / material, etc., and the MOM shall be signed by all parties. - Issues impact shall be reflected on the running/ current invoices.	PM	MOM (F-P-QD-06-02) Deduction form (F-P-OP-05-05)
6.11	K. Weekly Reports Subcontractor should submit a weekly progress report indicating the following status - Shop Drawings Progress. - Procurement, Fabrication and Delivery status - Construction Progress and dates of IRs readiness. - Area of concerns	S/C	
6.12	L. House Keeping management process The S/C is responsible for submitting the house keeping management process as per Subcontract agreement clauses and RME Safety plan requirements which includes the following: Daily Housekeeping - Clean-up crew is to be organized for daily housekeeping. - All combustible waste materials are to be removed from the jobsite daily, or more often, if required by Safety personnel.	S/C	

Sr.	Process Cycle description	Responsibility	Form
	○ Suitable waste containers should be provided at various locations and emptied daily ○ Waste collection points are to be designated and maintained. ○ All refuse and rubbish in the dump area that will be disposed outside the jobsite, is to be decided by RME/client. ● Weekly Housekeeping ○ Weekly housekeeping is to be carried out every weekend (if needed). ○ S/C Supervisors in charge of each area are responsible to keep their concerned area always at acceptable level ○ Activities of weekly housekeeping will be carried-out the same as daily housekeeping. ○ Members of HSE Committee will make patrol of jobsite and other areas after weekly cleaning ● Special Housekeeping ○ Special housekeeping is carried-out upon the request of RME/client in case of long holidays or any other reason. ● Material Arrangement ○ Proper pathways between materials stored should always be established. ○ Proper stacking for materials is always a must. Over stacking is prohibited. ○ Segregation should be established between all materials and all areas should have labeling. ○ Storage racks should have labels. ○ Housekeeping is always required in storage areas.		

Sr.	Process Cycle description	Responsibility	Form
	○ All materials should be stored in designated storage areas only. ○ Fire extinguishers should be distributed in storage areas. ○ Storage areas will be regularly inspected. ○ Flammable/combustible materials are not allowed to be stored except in designated chemical/hazardous storage areas and have their MSDS posted. ● Permanent Materials ○ Will be transported to the construction site only in quantity approved by client and will be stacked and laid down in a neat and tidy manner. Materials do not obstruct access ways and other working areas. ● Temporary Materials ○ Such as form materials, scaffolding, plates, tubes, etc., is to be kept in a neat and tidy manner and removed from the jobsite on the completion of related work. ○ Storage areas must be adequate for all material and equipment to be stored, they should be clearly marked & will be kept clean and materials neatly stacked or placed. Materials will be stored or placed in an orderly manner. ○ Electric welding leads, cords, wires, electrical cables, hoses, and other temporary systems will be kept off the walking surface in an		

Sr.	Process Cycle description	Responsibility	Form
	elevated position they should have directional signs to facilitate speedy delivery.		
6.13	M. Snagging and Hand Over - After installation of all completed items, inspected and approved, internal snagging shall be carried out by the S/C to ensure that all work is done as per RME/Client requirements. - The S/C Engineer shall: - Carry out snagging and prepare internal snag list. - Coordinate the outstanding items with RME Construction Team. - Control snagging team to close snags. Raise Inspection Requests for RME/Client snagging and de-snagging.	S/C	Snag List F-P-OP-07-05
6.14	N. Operation and Maintenance Manual (OMM) - The S/C is responsible to ensure that OMM schedule has been set and OMM RME template has been utilised and maintained as per their scope of work. - Draft OMM shall be issued to RME for approval. - All completed OMMs shall be submitted to the Client as per contract specification and project requirements through RME.	S/C	OMM F-P-OP-07-04
7	S/C Evaluation (Refer to process (P-PR-02)) The performance of S/C shall be monitored periodically every 3 months in case it is a short-term project (less than 6 months) and 6 months for a	PM Concerned Parties	

	Subcontractor Management Process		
	Effective Date: Dec, 2021	Rev. No.: 00	Doc. No.: P-OP-01

Sr.	Process Cycle description	Responsibility	Form
	normal/ long term project, effective from the commencement date (or before the said period, if required).		

6.3. PROCESS OUTPUT

- Audit Report
- S/C evaluation
- MOM

7. – PROCESS RISK ASSESSMENT

- Included in the Risk register form no. F-P-QD-05-01 “Risk Identification and assessment” maintained by HOD to address risks and opportunities”

8. – PROCESS CONTROL

- Progress weekly Meetings to monitor S/C progress and issues
- IR and NCR log
- Weekly reports

9. PERFORMANCE MEASURE

- Periodic evaluation for the S/C
- Audit Report
- Actual progress VS planned

10.– DOCUMENT CHANGE HISTORY

No.	Revision Level	Description of changes	Effective Date
1	00	New Issue	Dec, 2021