



ROWAD
MODERN ENGINEERING

Concrete Pouring Process P-OP-08

Prepared By:

Yasser Zohny
Direct Award Manager

12/5/2024

Sameh El-Herazy
Quality Control Department Manager

Reviwd By:

Mahmoud Mahlab
Operations Manager

Approved By:

Mohamed Mahlab
CEO

May, 2024

Takky El-Din Mohamed
Technical Affairs Manager

Adham Edward
Purchasing Manager

Azhar
3-5-24

Mohamed Ragab
COO

	Concrete Pouring Process		
	Effective Date: May, 2024	Rev. No.: 01	Doc. No.: P-OP-08

1. OBJECTIVES

The objective of this process is to control and follow up the actual supplied and poured quantities vs theoretical quantities according to SD.

2. STAKEHOLDER

- Construction
- Technical Office
- Operation
- Warehouse
- Quality Control
- Batch Plant
- Third Party Laboratory
- Purchasing

3. LIABLE STAKEHOLDER

- Construction
- Quality Control
- Technical Office
- Operation
- Third Party Laboratory
- Purchasing
- Projects Control

4. TERMS AND DEFINITION

- TO: Technical Office
- STO: Site Technical Office
- SD: Shop Drawing
- PO: Purchase Order
- QC: Quality Control
- PM: Project Manager

5. RELATED DOCUMENTED INFORMATION

- Concrete Pouring Notification, F-P-OP-08-01
- Pouring Register Form, F-P-OP-08-02
- Concrete Wastage Report, F-P-OP-08-03
- Concrete Pouring Plan, F-P-OP-08-04
- Concrete Break Down Analysis, F-P-OP-08-05
- Subcontractor Invoice, F-P-OP-05-06

	Concrete Pouring Process		
	Effective Date: May, 2024	Rev. No.: 01	Doc. No.: P-OP-08

6. PROCESS DETAILS

6.1 PROCESS INPUT

- Quantity Surveyor
- Approved Quantity
- Laboratory Tests
- Concrete Voucher
- Concrete Ticket

6.2 Process Operations

Sr.	Process Cycle Description	Responsibility	Form
1	General agreement to be prepared for all approved concrete companies/concrete suppliers including the following: • General and special conditions • Payment terms • Wastage percentage Refer to Evaluation of External Providers Process (P-PR-02) The general agreement shall be signed by Purchasing & concrete companies.		
2	PR shall be issued through ORACLE system by project's requester as per the concrete histogram which received form Projects Control department on a monthly basis. PR to be issued 10 days prior to the activity start date. CS to be prepared accordingly refer to "Purchasing Process P-PU-01"	Project's Requester Projects Control	Concrete Histogram
3	Concrete Break Down Analysis to be prepared based on the prepared CS by Purchasing department, then negotiation shall be done with suppliers to reduce the difference between suppliers' price and Rowad's reference price. Final Concrete Break Down Analysis to be approved by Purchasing HoD & COO.	Purchasing COO	Concrete Break Down Analysis F-P-OP-08-05
4	Relevant POs shall be issued partially according to the concrete histogram and signed agreement, agreement number to be mentioned in each PO.	Purchasing	
5	Concrete pouring plan for major elements shall be prepared by Construction team 2 weeks prior pouring activity, then approved by Quality Control.	Construction Team Quality Control	Concrete Pouring Plan F-P-OP-08-04

	Concrete Pouring Process		
	Effective Date: May, 2024	Rev. No.: 01	Doc. No.: P-OP-08

Sr.	Process Cycle Description	Responsibility	Form
6	Construction shall notify TO about concrete pouring and request the estimated quantity using "Concrete Pouring Notification" 48 hours prior to pouring planned date.	Construction Engineer	Concrete Pouring Notification F-P-OP-08-01
7	TO Engineer shall estimate the quantities (M ³) of concrete elements as per the SD including the losses percentage, then send it to the construction team on the same day and states his comments, if any.	TO Engineer	Concrete Pouring Notification F-P-OP-08-01
8	Construction engineer shall send the "Pouring Notification" to the QC for coordination with the relevant lab as well as stating his comments, if any.	Construction Engineer	Concrete Pouring Notification F-P-OP-08-01
9	Construction engineer shall coordinate with the approved batch plant for the required quantities, after confirming with the Purchasing department. Concrete pouring shall not proceed before receiving the client's approved IR for the concrete elements.	Construction Engineer	
10	The concrete truck arrives at the site's gate with the original supply voucher with two carbon copies and the concrete ticket.		
11	The concrete truck shall pass by the laboratory, or the place of casting as coordinated with the QC to perform the necessary required site tests. If concrete is accepted, the QC/Lab shall sign the voucher.	QC/Lab	
12	Construction Engineer/Supervisor shall approve and sign the concrete voucher after pouring the truck, deduction to be mentioned on the voucher, if any. If any quantity is used in temporary work/mobilization, the site engineer shall mention the quantity on the voucher.	Construction Engineer/Supervisor	
13	Construction shall deliver the voucher to the warehouse with both QC/Lab and construction's signature, warehouse to verify both signatures prior data entry on Oracle.	Construction Engineer/Supervisor Warehouse	
14	QC/Lab shall register the voucher number, truck's plate, etc. in the Pouring Register Form, then send it the next day to the TO. Soft copy for the cumulative week to be sent to TO.	QC/Lab	Pouring Register Form F-P-OP-08-02

	Concrete Pouring Process		
	Effective Date: May, 2024	Rev. No.: 01	Doc. No.: P-OP-08

Sr.	Process Cycle Description	Responsibility	Form
15	Random quantity inspections to be conducted on the received trucks vs the calculated elements, requested by PM, in coordination with QC, TO and Construction.	PM QC TO Construction Team	
16	Concrete suppliers shall submit work completed status along with the concrete voucher within 14 days from pouring date.		
17	STO shall send an email to each supplier within 7 days from receiving supplier's documents to inform him/her with the actual QS and the deduction amount due to the actual concrete losses., if any.	STO	
18	STO shall prepare concrete wastage report including the pouring data, the actual quantities, etc., then invoice to be issued considering the actual concrete amount losses within 7 days from the sent email to be signed by supplier.	STO	Subcontractor Invoice F-P-OP-05-06 Concrete Wastage Report F-P-OP-08-03
19	STO shall send the invoice to H.O. T.O to proceed with the relevant signatures within 3-5 days, then send it to the Purchasing Accountants. In parallel supplier shall issue the electronic bill to the Purchasing Accountants for review.	STO	Subcontractor Invoice F-P-OP-05-06
20	Signed invoice along with the electronic bill to be sent by Purchasing to Finance to proceed with payment.	Purchasing	Subcontractor Invoice F-P-OP-05-06
21	In case of inflation addendum: Purchasing shall prepare comparison sheet with a minimum of three suppliers and concrete price breakdown analysis. Refer to Purchasing Process (P-PU-01)	Purchasing	Supply Engineering Material-CS F-P-VMO-01-02 Concrete Break Down analysis F-P-OP-08-05

6.3 PROCESS OUTPUT

- Actual losses concrete quantities.
- Supplier Invoice.

	Concrete Pouring Process		
	Effective Date: May, 2024	Rev. No.: 01	Doc. No.: P-OP-08

7. PROCESS RISK ASSESSMENT

Included in the risk register form No. F-P-QD-05-01 “Risk identification and assessment” maintained by the HOD, along with the action plan to address risks and opportunities”.

8. PROCESS CONTROL

- Concrete follow-up sheet vs theoretical calculation out of approved SD.

9. PERFORMANCE MEASURES

- Wastage Report.

10. DOCUMENT CHANGE HISTORY

No.	Revision Level	Description of Changes	Effective Date
01	00	New Issue	March, 2022
02	01	Points (1-5, 9 & 16-21)	May, 2024