



ROWAD
MODERN ENGINEERING

Quality Plan Inspection and Testing Process P-QD-12

Prepared by:

Sameh Herazy

Quality Control Dept. Mgr.

Mahmoud Mahlab

Operation Mgr.

Reviewed by:

Mohamed Ragab

COO

Approved by:

Mohamed Mahlab

CEO

Dec, 2021

	Quality Plan, Inspection and Testing		
	Effective Date: Dec, 2021	Rev. no.: 00	Doc. no.: P-QD-12

1. OBJECTIVES

The objective of this process is to describe the inspection process and supporting documents, and to ensure that the inspection and test status of all work in the project is controlled in accordance with the project specification requirements and known at all stages of the construction process.

2. STAKEHOLDER

- Client
- Subcontractor /Supplier
- Construction
- QC
- Third Party Testing Laboratories
- DC

3. LIABLE STAKEHOLDER

- Subcontractor
- Construction
- QC
- Third Party Testing Laboratories
- DC

4. TERMS AND DEFINITION

- **QC:** Quality Control
- **QCM:** Quality Control Manager
- **PM:** Project Manager
- **DC:** Document Control
- **RME:** Rowad Modern Engineering
- **ITL:** Independent Testing Laboratory
- **ITP:** Inspection and Test Plan
- **IR:** Inspection Request
- **IIR:** Internal Inspection Request
- **PQP:** Project Quality Plan

	Quality Plan, Inspection and Testing		
	Effective Date: Dec, 2021	Rev. no.: 00	Doc. no.: P-QD-12

- **KPI:** Key Performance Indicator
- **Witness (W):** Consultant may witness, or inspect the work, while the works will proceed if not inspected no documentation required.
- **Document Review (R):** Documents to be reviewed, no signature required on the Inspection Request or its accompanying documentation.
- **Surveillance (S):** Random inspection at site, no documentation required.
- **Hold point (H):** The work will not proceed until the inspection is carried out.
- **Document Review:** Documents to be reviewed, no signature required on the Inspection Request or its accompanying documentation.

5. RELATED DOCUMENTED INFORMATION

- ITP form no. F-P-QD-07-06
- ITP Log F-P-QD-12-01
- Internal IR form F-P-QD-07-02
- IR form no. F-PQP-01-05
- IR Log no. F-P-QD-07-04

6. PROCESS DETAILS

6.1 PROCESS INPUT

- Contract Specifications
- Method Statement
- Standards/Codes
- Drawings

6.2 Process Operations

Sr.	Process Cycle Description	Responsibility	Form
1	PREPARATION AND APPROVAL OF PROJECT QUALITY PLAN (PQP) QC Manager shall prepare the project's quality plan within 15 days from the operation coordination meeting, and as per PQP 01 template and forms (last revision at the company server). The minimum requirements of PQP shall include the following:	QCM	PQP-01

	Quality Plan, Inspection and Testing		
	Effective Date: Dec, 2021	Rev. no.: 00	Doc. no.: P-QD-12

	• Quality Policy • Quality Objectives • KPIs • Project's Organization Chart • Job description of key staff • Incoming Material Control • Inspection and Testing Procedures • Quality Reports (Daily - Weekly - Monthly) • Data and Document Control • Internal Audit Process • Improvement Process • Evaluation of Subcontractors and Suppliers • List of Method Statements • List of ITPs and relevant checklists • List of forms in the project		
2	The PQP shall refer to RME quality management system processes. The PQP is a controlled document. The draft document for submission to the client shall be coded as "Revision 0". Thereafter, revisions shall be numerical. The approval of the PQP is the responsibility of QC Manager, approved by QC dept manager and PM.	QCM QC Dept. Mgr. PM	PQP-01
3	QC shall obtain inspection requirements from the following sources: • Contract Requirements • Project Specifications • Issued for Construction Drawings • Approved Shop Drawings • Related Local Standards/Codes	QC	

	Quality Plan, Inspection and Testing		
	Effective Date: Dec, 2021	Rev. no.: 00	Doc. no.: P-QD-12

	• Related International Standards/Codes (ACI, BS, etc.), if stipulated. • Applicable Method Statement refer to “Control of Production Process” P-QD-09. • Material Datasheet • Others		
4	QC Manager shall develop and maintain a list of ITPs for the project activities and shall schedule their submission dates.	QCM	ITP Log F-P-QD-12-01
5	The ITP shall contain and list the following: • Quality related activities to be conducted • Reference documents to be used, and all characteristics to be briefed • Acceptance criteria • The verifying document on which to record the activity • Tests and tests frequency Persons/parties to be present for witness sampling, inspecting, testing, etc.		ITP F-P-QD-07-06
6	ITPs are controlled documents and shall be prepared and coded as mentioned in the Project Quality Plan template – PQP 01. The draft document for submission to the client shall be coded as Revision 0. Thereafter, revisions shall be numerical. The document shall be revised to the next revision number whenever a change is made this includes changes to any form attached.	DC	ITP F-P-QD-07-06 PQP
7	ITPs shall be issued by the QC and approved by the client.	QC	ITP F-P-QD-07-06

	Quality Plan, Inspection and Testing		
	Effective Date: Dec, 2021	Rev. no.: 00	Doc. no.: P-QD-12

8	Subsequent revisions to ITPs shall be prepared by QC as necessary.	QC	ITP F-P-QD-07-06
9	ITPs shall be issued for implementation prior work commencement on site.	QC	ITP F-P-QD-07-06
10	Approved ITP is distributed to all concerned parties by the Document Controller. The Senior QC Engineer is responsible for ensuring the following actions on the ITP: - All inspection/ tests are carried out and recorded on appropriate (IR) forms with all relevant details. - All required personnel have signed and dated the verifying document attached to the relevant ITP. - All supporting reports, documents, certificate, etc. are attached.	DC QC Engineer Concerned Parties	ITP F-P-QD-07-06 IR F-PQP-01-05
11	INSPECTION PROCESS ON SITE The pre-construction approved mockup details shall be served as a reference during erection and inspection. The inspection test plan (ITP) shall be served as a plan for the related inspection and testing activities. Once the work is ready for inspection, Site Engineer shall inform QC 1 day prior to the inspection via Internal IR. Internal QC inspection shall take place at locations where defined using the relevant checklist and according to ITP.	Site Engineer QC	ITP F-P-QD-07-06 Internal IR F-P-QD-07-02

	Quality Plan, Inspection and Testing		
	Effective Date: Dec, 2021	Rev. no.: 00	Doc. no.: P-QD-12

	If the work item is not complying with the specification requirements, the QC Engineer shall reject the internal IR and inform the Site Engineer with his comments. The QC Engineer shall ensure that all his comments are fulfilled prior to client inspection. When internal inspection is approved, QC engineer shall issue Inspection Request to the client for inspection. IR log to be updated accordingly.	QC Site Engineer QC Engineer DC	IR F-PQP-01-05 IR Log F-P-QD-07-04
12	INDEPENDENT TEST LABORATORIES (ITL) Laboratory testing on-site may be delegated to an independent testing laboratory to be approved by the Client. Laboratory shall work to its own quality procedures concerning use, maintenance and calibration of all equipment and molds in accordance with relevant standard. The ITL responsibilities shall be defined in the applicable ITPs. Prior to its implementation all forms of laboratory test results shall be submitted to the QC manager for his review and approval. Prior to start of work, RME's Quality Control Engineer or QC Manager on site shall ensure that all equipment of ITL are well functioning and comply with the project's specification and recognized standards.	Laboratory Representative QCM QC Engineer/QCM	ITL

	Quality Plan, Inspection and Testing		
	Effective Date: Dec, 2021	Rev. no.: 00	Doc. no.: P-QD-12

Before obtaining Client's approval, ITL shall submit the resume of the site staff (engineers or technicians) to obtain approval from QC manager. All test reports shall be signed by the authorized Laboratory Engineer on site. All test reports specified in the ITP and complied by the Laboratory's engineer shall be transmitted to Document Controller.	ITL QCM Laboratory Engineer DC	
--	--	--

6.3 PROCESS OUTPUT

- Inspection and Test Plan (ITP)
- Internal Inspection Request (IIR)
- Inspection Request (IR)
- Project Quality Plan (PQP)

7. PROCESS RISK ASSESMENT

Included in the risk register form no. F-P-QD-05-01 "Risk identification and assessment" maintained by the HoD, along with the action plan to address risks and opportunities".

8. PROCESS CONTROL

QCM and PM shall ensure that ITP and PQP are fully implemented during project execution.

9. PERFORMANCE MEASURES

QC Manager shall monitor the construction/inspection process through the percentage of acceptance/rejection of inspection request.

10. DOCUMENT CHANGE HISTORY

No.	Revision Level	Description of Changes	Effective Date
01	00	New Issue	01/12/2021